

# 1x1 MURALS 32 SQUARES TOTALS

DIFFICULTY: **EASY**



CAN VARY



2 HOURS

## MATERIALS

### PREP

(1) .5x4x8" sanded plywood

1 gallon primer

9" roller, pad, and tray

### BUILD

(32) 12" plywood squares  
*\*cut during prep instructions*

128 zip ties (optional)

Paint brushes

Exterior paint

Drop cloth

Paint can opener

Stirring sticks

Paint cups

Latex gloves

## TOOLS

### PREP

Circular saw

Tape measure

Pencils

String line

### BUILD

Drill

.25" drill bit

Safety glasses

## PREP LIST

1. Sort all the materials into piles by like items to ensure you have materials needed to complete project.
2. Using the string line, lay out (32) 12x12" squares on the 4x6ft sheet of sanded plywood.
3. Using the circular saw to cut the plywood into 32 squares. Be sure to wear safety goggles while operation saw.
4. Paint the plywood squares with exterior primer on all sides.
5. Let primer dry before moving pieces.

## BUILD LIST

1. Sort all the materials into piles by like items to ensure you have materials needed to complete project.
2. Drill holes with the .25" drill bit about 1" into each corner of the 1x1 mural pieces. Be sure to wear safety goggles while using drill.
3. Lay out drop cloths under working area.
4. Decide if you'd like to use a theme to create a mosaic mural, or paint unique mini-murals. Supervise the children as they paint!
5. Allow squares to dry. Attach to fence or other desired location with zip-ties, screws, or wires.